



## RIO TINTO IRON ORE (RTIO) Parker Point Fuel Terminal North and South Bund SMPECI Works

LOCATION	DURATION	VALUE	MAN HOURS
Karratha, WA	Dec 2014 - Nov 2015	\$7.2 million	20,500

### Project Overview

The Parker Point Fuel Terminal is located at the RTIO Dampier facility in Western Australia. Due to an expansion of its current iron ore operations, RTIO forecasted requirements for diesel to increase by more than 50 per cent over three years, requiring an upgrade to its fuel storage and distribution facilities.

As part of the upgrade, ECM was awarded the structural, mechanical and piping works contract to install RT and RTC pumps and filters, oily water sump pumps, oily water separation system, Stadis dosing system, pipework and supports. It also includes the fabrication and installation of platforms, walk ways, handrails and stairs for the north and south bund areas.

ECM was also awarded the EC&I contract to install cables ladders, cabling and instrumentation to the RTG and RTC pumps, oily water sump pumps, oily water separation system, Stadis dosing system, tanks, and other associated equipment.

### Scope of Work

- Supply, delivery to site and installation of cable ladders, cabling, and instrumentation.
- Installation of RT and RTC pumps and filters, oily water sump pumps, oily water separation system, Stadis dosing system, pipework, supports and other associated equipment.
- Fabrication and installation of platforms, walk ways, handrails and stairs.
- Supply of all labour, transport, supervision, plant, services and materials for the procurement, fabrication, manufacture and installation of all equipment and components.
- Setting out, construction, testing, auditing and inspection of the works.
- Installation of company supplied equipment and materials.